

# TECO W Westinghouse

ISSUED

**April 4, 2013** 

TYPE

**AEGP** 

#### **PERFORMANCE DATA**

**3-PHASE INDUCTION MOTOR** 

**ENCLOSURE** 

**TEFC** 

CATALOG#

WP1/52C

N	ΔM	FPI	<b>ATF</b>	INFO	ORM	ΔΤΙ	ON
					<i></i>	$\overline{}$	

ſ	OU	TPUT	POLE	FRAME	VOLTAGE	HZ	RATED	INS.	NEMA	TIME	SERVICE
	HP	KW	POLE	SIZE	VOLTAGE	٦٧	AMBIENT	CLASS	DESIGN	RATING	FACTOR
ſ	1.5	1.12	2	145TC	230/460	60	40°C	F	В	CONT.	1.15

#### **TYPICAL PERFORMANCE**

FULL	EFFICIENCY				PO	WER FACT	OR	MAXIMUM
LOAD	FULL	LOAD	3/4 LOAD	1/2 LOAD	F. L.	3/4 LOAD	1/2 LOAD	POWER FACTOR
RPM	MIN. %	NOM. %	%	%	%	%	%	CORRECTION
3500	84	81.5	83	78	90	86	78	1 KVAR

NEMA	CURRENTS								
KVA	LOCKED ROTOR			)	FULL LOAD			NO LOAD	ľ
CODE	AT	AT	AT	AT	AT	AT	AT	AT	AT
LETTER	460	230	208	460	230	208	460	230	208
LETTER	VOLT	VOLT	VOLT	VOLT	VOLT	VOLT	VOLT	VOLT	VOLT
М	20.00	40.00	44.23	2.00	4.00	4.20	0.80	1.60	1.77

TORQUE				INERTIA			ACCEL TIME	
FULL LOAD lb-ft	LOCKED ROTOR %FLT	PULL UP %FLT	BREAK DOWN %FLT	ROTOR WR <sup>2</sup> lb-ft <sup>2</sup>	NEMA LOAD WK <sup>2</sup> lb-ft <sup>2</sup>	MAX ALLOWABLE WK <sup>2</sup> lb-ft <sup>2</sup>	NEMA LOAD WK <sup>2</sup> Sec	MAX ALLOWABLE WK <sup>2</sup> Sec
2.3	250	260	300	0.07261	1.8	2	3.70	4.10

SAFE S	TALL	ALLOV	VABLE	SOUND
TIME	IN	STA	RTS	PRESSURE
SECO	NDS	PER I	HOUR	LEVEL @ 3 FT
COLD	HOT	COLD	HOT	dB(A)
12	10	2	1	76

APPROVED:	M. PRATER	DRAWING NO.	31057WP1/52C	REVISION	0
-----------	-----------	-------------	--------------	----------	---

DATE:


April 4, 2013


#### **CONNECTION DIAGRAM**

CATALOG NO.:

WP1/52C

#### **ACROSS THE LINE CONNECTION**





LINE 230 VOLT CONNECTION

LINE
460 VOLT CONNECTION




DWG NO.

**DAC-1566-2** 

# INSTALLATION AND MAINTENANCE INSTRUCTIONS FOR THREE PHASE INDUCTION MOTORS

#### Frames 143T - 449TZ





#### RECEIVING

- 1. Check nameplate data.
- 2. Check whether any damage has occurred during transportation.
- 3. Turn shaft by hand to check that it turns freely.
- 4. If motor is to be reshipped (alone or installed to another piece of equipment) the shaft must again be clamped to prevent axial movement.

Note: Remove the bearing clamp before turning the shaft of 284-T-445T frame motors.

# WARNING THE FOLLOWING SAFETY PRECAUTIONS MUST BE OBSERVED:

- 1. Electric rotating machinery and high voltage can cause serious or fatal injury if improperly installed, operated or maintained. Responsible personnel should be familiarized with NEMA MG2: Safety Standards for Construction and Guide for Selection. Installation and Use of Electric Motors and Generators; National Electric Code and all local safety requirements.
- When servicing all power sources to the motor and to the accessory devices should be de-energized and disconnected and all rotating parts should be at standstill.
- Lifting means, when supplied, are intended for lifting the motor only.
   When two lifting devices are supplied with the motor a dual chain must be used.
- 4. Suitable protection must be used when working near machinery with high noise levels.
- 5. Safeguard or protective devices must not be by-passed or rendered inoperative.
- 6. The frame of this machine must be grounded in accordance with the National Electrical Code and applicable local codes.
- 7. A suitable enclosure should be provided to prevent access to the motor by other than authorized personnel. Extra caution should be observed around motors that are automatically or have automatic resetting relays as they may restart unexpectedly.
- 8. Shaft key must be fully captive or remove before motor is started.

- Provide proper safeguards for personnel against possible failure of motor-mounted brake, particularly on applications involving overhauling loads.
- 10. Explosion proof motors are constructed to comply with the label service procedure manual, repair of those motors must be made by TECO-WESTINGHOUSE or U/L listed service center in order to maintain U/L listing.

#### LOCATION

- 1. Drip-proof motors are intended for use where atmosphere is relatively clean, dry, well ventilation and non-corrosive.
- 2. Totally enclosed motors may be installed where dirt, moisture, or dust present and in outdoor locations.
- 3. Explosion-proof motors are built for use in hazardous locations as indicated by Underwriters' label on the motor.
- 4. Chemical duty enclosed motors are design for installation in high corrosion or excessive moisture locations.

Note: in all cases, no surrounding structure should obstruct normal flow of ventilating air through or over the motor.

#### MOUNTING

- Mount motor securely on a firm, flat base. All ball bearing normail thrust motors up to and including 256T frame size, may be sidewall or ceiling mounted: all others, check nearest TECO-WESTINGHOUSE office for mounting recommendations.
- 2. Align motor accurately, using a flexible coupling if possible. For drive recommendations, consult with drive or equipment manufacturer, or TECO-WESTINGHOUSE.
- 3. Mounting bolts must be carefully tightened to prevent changes in alignment and possible damage to the equipment. The recommended tightening torques for medium carbon steel bolts, identified by three radial lines at 120 degrees on the head, are:

Dall Cine	Recommended Torque(Ft-1b)				
Bolt Size	Minimum	Maximun			
2/8	25	37			
1/2	60	90			
5/8	120	180			
3/4	210	320			

4. V-belt Sheave Pitch Diameters should not be less than the following Table 1. values (NEMA recommended values).

table 1.V-belt sheave Pitch Diameters(MG1-14.42)

Frame			epower at nous Speed. Rpn	
Number		Synchroi	nous Speed. Kpii	
(10111201	3600	1800	1200	900
143T 145T 182T 182T 184T 184T 184T	1 1/2 2-3 3 5  5 7 1/2	1 1 1/2-2 3   5	3/4 1 1 1/2  2 	1/2 3/4 1 1 1 1/2 
213T 215T 215T 254T 254T 256T 256T	7 1/2-10 10 15 15 20 20-25	7 1/2  10  15  20	3 5  7 1/2  10 	2 3  5  7 1/2 
284T 284T 286T 324T 326T 364T 364T 365T		 25 30 40 50  60  75	15  20 25 30 40  50	10  15 20 25 30  40
404T 404T 404T 405T 405T 405T		 100  100 125	60   75 	50  60 
444T 444T 444T 444T 445T 445T		 125 150  150	100   125 	 75    100

<sup>\*</sup>Max. Sheave width = 2(N-W).  $\frac{1}{4}$ "

<sup>\*\*</sup>Max. Sheave width = N.W.

<sup>\*</sup>Sheave ratios greater than 5:1 and center-to-center distance less than the diameter of the large sheave should be referred to the company

5. Tighten belts only enough to prevent slippage. Belt speed should not exceed 5000 ft. Per min.

	V bol	olt Sheave			
	entional D. and E	<u>Nar</u> 3V.5V.a	row		
Minimum Pitch Diameter Inches	*Maximum  Width Inches	Minimum Outside Diameter Inches	**3 Maximum Width. Inches		
2.2 2.4 2.4 2.6 2.4 2.6 3.0	4 1/4 4 1/4 5 1/4 5 1/4 5 1/4 5 1/4 5 1/4	2.2 2.4 2.4 2.4 2.4 2.4 3.0	2 1/4 2 1/4 2 3/4 2 3/4 2 3/4 2 3/4 2 3/4		
3.0 3.0 3.8 3.8 4.4 4.4 4.6	6 1/2 6 1/2 6 1/2 7 3/4 7 3/4 7 3/4 7 3/4	3.0 3.8 3.8 4.4 4.4 4.4	3 3/8 3 3/8 3 3/8 4 4 4 4		
4.6 5.0 5.4 6.0 6.8 6.8 7.4 8.2 9.0	9 9 9 10 1/4 10 1/4 11 1/2 11 1/2 11 1/2	4.4 4.4 5.2 6.0 6.8 6.8 7.4 8.2 8.6	4 5/8 4 5/8 4 5/8 5 1/4 5 1/4 5 5 7/8 5 7/8 5 7/8		
9.0 9.0 10.0 10.0 10.0 11.5	14 1/4 14 1/4 14 1/4 14 1/4 14 1/4 14 1/4	8.0 8.4 8.6 10.0 8.6 10.5	7 1/4 7 1/4 7 1/4 7 1/4 7 1/4 7 1/4		
11.0 10.5 11.0  12.5 12.5	16 3/4 16 3/4 16 3/4 16 3/4 16 3/4 16 3/4 16 3/4	10.0 9.5 9.5 10.5 12.0 12.0 10.5	8 1/2 8 1/2 8 1/2 8 1/2 8 1/2 8 1/2 8 1/2		

#### POWER SUPPLY & CONNECTIONS.


- Wiring of motor and control, overload protection and grounding should be in accordance with national electrical code and all, Local safty requirements.
- 2. Nameplate voltage and frequency should agree with power supply. Motor will operate satisfactorily on line voltage within 10% of nameplate value, or frequency within 5% combined variation not to exceed 10%. 230 Volt motors can be used on 208-volt network systems, but with slightly modified performance characteristics as shown on nameplate.
- Dual voltage and single voltage motors can be connected for the desired voltage by following connection diagram shown on the nameplate or inside of the conduit box.
- 4. All Explosion Proof motors have Temperature Limiting Devices in the motor enclosure to prevent excessive external surface temperature of the motor in accordance with u/l standards. Terminals of thermal protectors (P1, P2) should be connected to the motor control equipment, according to the connection diagram inside of the conduit box.
- 5. Standard connection diagram for three phase, not thermally protected, dual rotation motors are shown as diagram A to E (Note: To dhange rotation. Interchange any two line leads)


A.3 Leads, Single Voltage

B.6 Leads, Dual Voltage & Voltage Ratio 1to√3

B-1. Across The Line Start &Run

B-2. Wye Start & Delta Run (Low Voltage only)





C.9 lead, Dual Voltage & Voltage Ratio 1 to 2. Wye connected.
C-1. Across The Line Start C-2. Part Winding Start
& Run (Low Voltage only)

Low Voltage( 2人)	High Voltage(人)
L1 L2 L3 T10 T2 T3 T70 T80 T90 T4 T5 T6	L1 L2 L3 T10 T20 T30 T70 T80 T90 T40 T50 T60

<u>L1</u>		, M1	_T7		START	RUN
		М2	 T1	M1	CLOSE	CLOSE
12	Ь——	M1	- • •	M2	OPEN	CLOSE
<u></u>	—		-T8	Tie	(T4 -T	5 -T6)
	L	M2 ⊢——	_T27	Togeth	er`	,
<u>L3</u>	<del></del>	M1	-T9			
		M2	TO			
4	·	<del></del>	-13			

D.9 lead, Dual Voltage & Voltage Ratio 1 to 2. Delta connected.
D-1. Across The Line Start D-2. Part Winding Start
& Run (Low Voltage only)


Low Voltage(2△)	High Voltage(△)		
L1 L2 L3	L1 L2 L3		
T10 T20 T30	T18 T28 T38 T8		
17¢ T5¢ T8¢	17° T5°—°		
T6 T9 T4	T60 T9 T40		

(						
L1,		M1	_T1-T6		START	<u> RUN</u>
		M2		M1	CLOSE	CLOSE
		<del>- 1412.</del>	_ 1 /	M2	OPEN	CLOSE
L2,		. M1	-T4-T8	14122	Of EIV	CLOCL
$\overline{}$	,		-14-10	ļ		
		_M2	-T2			
L3	,	M1				
	Т	<del></del>	-T3			
		M2				
ŀ	Ь——	1	-T5 <b>-</b> T9			

E.12 Leads, Dual Voltage E-1.Across The Line Start & Run


Lo	Low Voltage(2△)		High Voltage(△)				
	<u>,</u> 1	L2	L3			L2	L3
T1	T2 '	T3 '	ļ	T1		Тэ	1
17	Т8 '	Т9		T12	T10	T11	ļ
T6	T4 (	T5 °		T69	74°	የ <b>T</b> 5	P
T12	T12 T10 T11		T9 T7 T8				
L							

E-2. Wye Start & Delta Run E-2-1. Low Voltage




	START	RUN
M1	CLOSE	CLOSE
M2	OPEN	CLOSE
МЗ	CLOSE	OPEN

#### E-2-2. High Voltage



	START	RUN		
M1	CLOSE	CLOSE		
M2	OPEN	CLOSE		
МЗ	CLOSE	OPEN		
Tle Together(T4-T7).(T5-T8).(T6-T9)				

#### E-3.Part Winding Start(Low Voltage only)



	START	RUN
M1	CLOSE	CLOSE
M2	OPEN	CLOSE

- \*Important: For Part Winding Start, M2 contactor should be closed within two (2)seconds after M1 contactor is closed.
- \*Only 4 poles and above (e. g. 6p, 8P···) Motors are satisfactory for part winding start at low voltage.

#### START UP

- 1. Disconnect load and start motor. Check direction of rotation. If rotation must be changed, ALLOW THE MOTOR TO STOP COMPLETELY. Interchange any two leads of a three phase motor.
- 2. Connect load. The motor should start quickly and run smoothly. If not, shut power off at once. Recheck the assembly including all connections before restarting.
- If excessive vibration is noted, check for loose mounting bolts, too flexible motor support structure or transmitted vibration from adjacent machinery. Periodic vibration checks should be made, foundations often settle
- 4. Operate under load for short period of time; check operating current against nameplate.

#### **TESTING**

If the motor has been in storage for an extensive period or has been subjected to adverse moisture conditions, it is best to check the insulation resistance of the stator winding with a megohmeter. Depending on the length and conditions of storage it may be necessary to regrease or change rusted bearings.

If the resistance is lower than one megohm the windings should be dridd in one of the two following ways;

- 1) Bake in oven at temperatures not exceeding 194 degree F until insulation resistance becomes constant.
- 2) With rotor locked, apply low voltage and gradually increase current through windings until temperature measured with thermometer reaches 194 degree F. Do not exceed this temperature.

### MAINTENANCE INSPECTION

Inspect motor at regular intervals. Keep motor clean and ventilation openings clear.

#### LUBRICATION

- 1 Frame 143T-256T: Double shield and prelubricated ball-bearing motors without grease fittings and don't need relubrication.
- 2 Frame 280TS, 320-445T&S: motors having grease fittings and grease discharge devices at brackets. Motors are shipped with grease fou initial running. It is necessary to relubricate anti-friction bearing motors periodically, depending on size and type of service, (see table 2) to provide maximum bearing life. Excessive or too frequent lubrication may damage the motor.

#### **TABLE2**

Horsepower	Standard	Severe	Extreme
	Conditions	Conditions	Conditions
1 THRU 30.1800 rpm and below	7 years	3 years	6 months 30 days 15 days 3 months 30 days 15 days
40 THRU 75.1800 rpm and below	210 days	70 days	
100 THRU 150.1800 rpm and below	90 days	30 days	
1 THRU 20.3600 rpm	5 years	2 years	
25 THRU 75.3600 rpm	180 days	60 days	
100 THRU 150.3600 rpm	90 days	30 days	

- Note: 1). Standard conditions: 8 hours operation per day, normal or light loading, clear and 40 degree C ambient conditions.
  - 2). Severe conditions: 24 hours operation per day or light shock loading, vibration or in dirt or dust conditions.
  - 3). Extreme conditions: With heavy shock or vibration or dust conditions.
  - 4). For double shield bearing, above data (lubrication frequency) mean that the bearing must be replaced.
- 3. Be sure fittings are clean and free from dirt. Using a low-pressure grease gun, pump in the recommended grease until new grease appears at grease discharge hole.
- 4. Use the ALVANIA R3 grease or equivalent lithium based grease unless a special grease is specified on the nameplate.
- 5. If relubrication is to be performed with the motor running, stay clear of rotating parts, After regreasing, allow the motor to run for ten to thirty minutes.

#### **RENEWAL PARTS:**

- 1 Use only genuine TECO-WESTINGHOUSE renewal parts or as recommended by TECO-WESTINGHOUSE.
- 2. When you order renewal parts please specify complete information to TECO-WESTINGHOUSE. Office/agent such as type, frame NO., poles, horsepower series NO., quantity, etc.

## FOR FURTHER INFORMATION PLEASE CONTACT TECO-WESTINGHOUSE MOTOR COMPANY

 SALES OFFICE:
 Houston, TX
 (713) 864-5980

 Los Angeles, CA
 (714) 670-2722

 Spartanburg, SC
 (864) 576-0356

 Allentown, PA
 (610) 391-9690

 Portland, OR
 (503) 684-3363

HEAD QUARTER: Round Rock, TX (512) 255-4141

STANDARD WARRANTY FOR TECO-WESTINGHOUSE MOTORS ALL TECO-WESTINGHOUSE brand motors sold by TECO-WESTINGHOUSE MOTOR COMPANY are warranted to be free from defects in material and workmanship for a period of 36 months from the date of manufacture..

This warranty is conditioned upon the installation, operation, and maintenance of the motors in accordance with TECO-WESTING HOUSE MOTOR COMPANY's recommendations or standard industry practice and the motors have at all times being operated or used under normal operating conditions for which they were designed.

TECO-WESTINGHOUSE MOTOR COMPANY shall, at its sole option and expense, either repair or replace, F.O.B. warehouse, any such motor or part which is defective within the warranty period.

In the event of warranty claims. TECO-WESTINGHOUSE MOTOR COMPANY must be notified promptly following any motor failure. The motor shall be sent to a TECO-WESTINGHOUSE MOTOR COMPANY authorized service center fou diagnosis on the cause of failuer. If the failure is due to defective material and/or workmanship, TECO-WESTINGHOUSE MOTOR COMPANY will replace or repair the defective motor or part.

The repair or replacement of defective material and workmanship shall constitute complete fulfillment of TECO-WESTINGHOUSE MOTOR COMPANY's warranty liability whether the warranty claims are based on contract, tort (including negligence and strict liability), or otherwise.

THERE ARE NO OTHER WARRANTIES, EXPRESS OR IMPLIED, INCLUDING ANY IMPLIED WARRANTY OF MERCHANTABILITY AND FITNESS FOR PARTICULAR PURPOSE, AND ALL WARRANTIES ARISING FROM COURSE OF DEALING AND USAGE OF TRADE.

UNDER NO CIRCUMSTANCES, SHALL TECO-WESTINGHOUSE MOTOR COMPANY BE LIABLE FOR ANY SPECIAL, INDIRECT INCIDENTAL, OR CONSEQUENTIAL DAMAGES, INCLUDING FREIGHT